Sl. No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Parapet wall with stepped coping in burnt brick in mortar 9″ thick including white and colour washing	R.ft.	..	58	
15	Cement mortar plastering 1 : 4, ¾″ thick ..	Sqr.	..	12·13	
16	Lime mortar plastering (main building) ..	,,	..	10·50	
17	Flooring with 1½″ cement concrete over 3″ lime concrete 1 : 2 : 4, ½″ cement plastering, etc., complete	,,	..	4·31	
18	Government Lac Factory green paint 3 coats ..	,,	..	2·46	
19	White and colour washing 2 coats as per area of plastering	,,	..	23·80	

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. 15 *of* 1939-40, *dated* 30*th April* 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, up to 2 P.M. on 10th May 1940, for sinking a well for Somanahalli Agricultural School near Maddur.

2. An approximate estimate of quantities for the above work is given below. The quantities are not guaranteed. The work should be completed within one month from the date of acceptance of tender.

3. Earnest money of Rs. 50 in cash should be remitted under the Revenue Deposits, at the State Huzur Treasury, Bangalore, or Maddur Taluk Treasury, with a chellan duly filled in by the tenderer. The tender should be superscribed "tender for sinking a well for the Somanahalli Agricultural School near Maddur." The tenders will be opened at 2-30 P.M. on 10th May 1940.

4. Subject to formal sanction of the Director of Agriculture, the acceptance of the tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond in default of which his tender will be considered as cancelled and the security deposit forfeited.

6. The name of the successful competitor, whose tender has been accepted will be notified in due course.

7. After the acceptance of successful tender, the earnest money deposited on the refused tenders will be arranged to be returned to the parties.

8. Rates once tendered will on no account be enhanced.

9. Quotation must be written in words as well as in figures.

10. The measurements checked by the Agricultural Engineer, will have to be accepted as final.

Statement showing the approximate quantities of work.

Sinking a well for the Somanahalli Agricultural School near Maddur.

No.	Items of work	Unit	Quantity
1	Earthwork excavation in gravel	C.yd.	580
2	Excavation in hard gravel and disintegrated rock	C.yd.	547
3	Baling water and removing slush	Lump-sum	
4	Dry stone revetment	C.ft.	5,035
5	Stone slabs 6″ thick	S.ft.	590

M. G. SINGRACHAR,
Agricultural Engineer.